



2005 C&D Disposal Estimates

Tons	Tons	Tons	Total C&D
Disposed	Disposed	Disposed	Disposed
Via C&D	via	at Transfer	
Facilities	Intermodal	Stations	
199325.9	45,593	162,000	406,918.9

C&D Diversion/Recycling Rates at Mixed C&D Facilities

Incorporates monthly reporting data from WM, Allied, and Recovery 1 Facilities.

- Diversion rate: 12.28%
- Recycling rate: 4.71%





Goal of This Program

Divert the greatest amount of materials possible

- Without negatively impacting project schedule
- Without negatively impacting project budget
- Without increasing project liability







Strategies Overview

- Waste reduction (handout)
- Reuse
 - Salvage
 - Deconstruction
- Recycling



Salvage

Removing nonstructural items of value from a building.





Deconstruction

The process of taking down a building in such a way as to maintain the highest value practical of its components.





Beams



- Average beam yield per building = 150 lineal feet
- 150 lineal feet of 6x8 =600 board feet
- 600 board feet x \$0.70-0.95/board foot = \$420-570/building depending on condition/quality
- \$420-570/building x 100 buildings with 6x8 foundations = \$42,000.00 57,000.00

Recycling Pays

- Clean Wood: -\$30 + \$80 = \$50
- Concrete: -\$40 + \$80 = \$40
- Cardboard & Plastic Wrap: \$0 + \$80 = \$80
- Metal: Pays! Pays! Pays!



Recycling Saves Money

Alternative	Total C&D Debris Costs	Total Trucking Costs	Total Cost of Disposal
0% Recycling Rate	\$59,294.03	\$8,535.60	\$67,829.63
50% Recycling Rate (1 LEED Point)	\$49,633.76	\$4,836.84	\$54,470.60
60% Recycling Rate (Const. Works Min.)	\$47,701.71	\$4,097.09	\$51,798.80
75% Recycling Rate (2 LEED Points)	\$44,803.63	\$2,987.46	\$47,791.09
84% Recycling Rate (Projected Project Max.)	\$43,064.78	\$2,321.68	\$45,386.47



The Toolbox

- Specifications
- Requiring submittals
- C&D facility recycling rate web pages
- Scheduling (salvage/deconstruction)
- Hauling distance
- LEED
- ReStore salvage contract
- Technical assistance for project manager
- Project assistance for contractor

Specifications

- <u>Section 01505 Construction Waste</u>
 <u>Management</u> (<u>PDF</u>, 39 K) also used as Section 1524
- Section 01736 Building Deconstruction (and Salvage) (PDF, 26 K) - also used as Section 02050 or Section 024293 under 2004 CSI
- More to come.....

Submittals

Waste Management Report:

- 1. A record of the type and quantity, by weight, of each material salvaged, reused, recycled or disposed.
- 2. Total quantity of waste recycled as a percentage of total waste.
- 3. Disposal Receipts
- 4. Recycling Receipts
- 5. Salvaged Materials Documentation

Regional CDL Recycling Facilities & their Current Diversion/Recycling Rates – as Reported to King County					
Facility Name	Facility Recycling Rate 1	Appropriate for Processing Recycling Rate ²	Percentage of Diverted Materials Recycled ³	Percentages of D Beneficial U	iverted Materials to se 3
				Hog Fuel	<u>ADC</u>
Waste Management - Cascade Recycling Center	25.40%	49.50%	64.20%	17.70%	18.10%
Waste Management - Eastmont Recycling Center	23.60%	73.70%	84.00%	16.00%	0%
Waste Management - Recycling Northwest	0.74%	49.50%	25.70%	73.30%	0%
Rabanco - Black River	0%	0%	0%	0%	0%
Rabanco - 3rd & Lander	1.40%	3.90%	100%	0%	0%
Recovery 1	93.81%	91.91%	20.56%	60.46%	18.98%

Scheduling

- Salvage may occur prior to Notice to Proceed
- Allow ~1 extra week for full deconstruction
- Advance notice goes a long way!



Avoided Hauling Costs

Alternative	Total CDL Debris Costs	Total Trucking Costs	Total Cost of Disposal
0% Recycling Rate	\$59,294.03	\$8,535.60	\$67,829.63
50% Recycling Rate (1 LEED Point)	\$49,633.76	\$4,836.84	\$54,470.60
60% Recycling Rate (Const. Works Min.)	\$47,701.71	\$4,097.09	\$51,798.80
75% Recycling Rate (2 LEED Points)	\$44,803.63	\$2,987.46	\$47,791.09
84% Recycling Rate (Projected Project Max.)	\$43,064.78	\$2,321.68	\$45,386.47

LEED

- Materials and Resources Credit 2.1 50%
- Materials and Resources Credit 2.1 75%
- Innovation Credit 90%



ReStore Contract

- Covers light salvage to minor deconstruction
- Free service to the county
- Can conduct site assessment and provide itemized list of salvageable items
- Prefer 2 weeks notice
- Contracted to respond within 72 hours of notification
- Have not delayed any schedules to date

Assistance

- Technical assistance for project manager
- Project assistance for contractor

Kinley Deller
King County Green Tools
6-4434
kinley.deller@metrokc.gov



North Recovery Facility

- ReStore salvaged 10 tons at no cost to county
- Contractor salvaged 28 tons of beams
- Combined resale value of salvaged materials ~\$22,500
- Avoided \$2000 -\$3000 in disposal costs
- Could have saved \$26,000 -\$41,000 in disposal costs
- Strategies: Salvage and deconstruction



Harbor Island Fisher Mill



- Bid as a deconstruction project requiring 75% diversion
- Recovered 78% of nonconcrete materials
- Recovered 93% of all materials
- Over 178 tons of wood were salvaged for reuse
- Avoided disposal fees totaled \$40,000-\$60,000
- Strategies: Deconstruction and recycling

Pan Abode



- Diverted 5 tons of material from landfill
- Materials diverted: walls, floors, ceilings, cabinets and a bathtub
- \$ saved: The cost of demolition
- Diversion: Salvage and deconstruction



Program Impact

Project	Tons Diverted	CO2 Equivalents Diverted
NRF	38	
Harbor Island	180	
Brightwater	75	
PanAbode	5	
King County Subtotal	298	208 MTCE (Metric Ton Carbon Equivalent)*
Greenbridge	25	
DoubleTree Hotel at Southcenter	66	
Total	389 tons	272 MTCE (Metric Ton Carbon Equivalent)*

^{*} Calculated using EPA's WARM software (http://yosemite.epa.gov/oar/globalwarming.nsf/WARM?openform) assuming that all diverted materials were dimensional lumber which was recycled.

